

**NOTE TO SPECIFYING ARCHITECT REGARDING
SECTION 11075
DARKENING DRAPERIES AND DRAPERY TRACK
(VINYL LAMINATE AND WALKALONG TRACK)**

Opaque drapery and track required for complete darkening of a room.

Track is walkalong type with drapery stacking beyond the glass area.

Draperies overhang the sills to cut out light at the sills.

Frequently used in classrooms and multi-purpose rooms.

Indicate rooms that require darkening draperies.

Phone 800-548-8982 for clarification or assistance. No charge, of course.

**SECTION 11075
DARKENING DRAPERIES AND DRAPERY TRACK
(VINYL LAMINATE AND WALKALONG TRACK)**

PART 1—GENERAL

- 1.01 Contractor shall furnish and install draperies and drapery tracks in accordance with the following specification at all exterior windows in the rooms listed.
- 1.02 Products specified as the standard shall be manufactured by Janson Industries (Canton, OH; 800-548-8982; FAX 330-455-5919) or approved equal.

PART 2—MATERIALS

- 2.01 All darkening drapery shall be manufactured from flame resistant vinyl laminated polyester, pleated to 75 percent added fullness, hemmed on all edges and with 2-inch jute webbing at the top. Grommets, number 2, shall be inserted at pleats on centers of approximately 6-inches. Drapery shall be manufactured and installed to tracks specified next. Janson Endura, Coral Spotlight or Frankel plastic backed Nevada is acceptable for the darkening function.
- 2.02 Track shall be Janson DBL77 of institutional quality expected to function without failure for the lifetime of the building. Track shall be extruded aluminum and shall incorporate dual rails to provide a positive center overlap without the use of master carriers. End section of extrusion shall be 2.36-inches by 1.20-inches. Carriers shall have two-wheel construction with full swivel eye or hook, and shall be furnished on 6-inch centers, or as required to coordinate with the grommets in the drapery tops. Towlines or wands shall be provided for the leading edge of all drapery sections. Track shall be extruded aluminum. Track sections less than 28-ft shall have no mechanical splices.
- 2.03 Rooms to be provided with installed drapery and drapery track are the following:

PART 3--EXECUTION

- 3.01 Track shall be secured to the ceiling or to brackets mounted on vertical surfaces. Substrates above the ceiling shall be 1 x 5 wood grounds. Tracks shall extend for the full length of the rooms or as required so that stacked drapery shall be beyond the glass area if physical conditions permit. Substrates required for track installation will be furnished and installed by this contractor. Locate track in such manner that a plumb line from the centerline of the track allows clearance at the edge of the window sill wherever this condition is appropriate.
- 3.02 Installation shall be coordinated with the progress of the general construction. All of the necessary grounds, clip angles, and supports required shall be furnished by this contractor.

Track shall be installed as one operation, and draperies shall be installed as another operation after the building has been cleaned.

- 3.03 All work shall be executed using high standards of workmanship in fabrication and erection. The finished installation shall be complete and functional in every respect, and drapery shall be left ready for use.

END OF SECTION

11075-2